



Integral Capillary Concrete Waterproofing Systems

Project Reference.



Residential Basement. Rotherham UK

Description

This basement suffered from increasing amounts of water penetration at different times of the year?

Products Used.

All surfaces were cleaned with a wire brush and jet washed to provide an open pore surface. Minor cracks and joints between floors and walls were filled with Penecrete Mortar and finished with 2 coats of Penetron.

Unit J11, Hastingwood Industrial Park, Wood Lane, Erdington, Birmingham.B24 9QR
Telephone 07833-746550.Mail:smather@penetron.co.uk. Web: www.penetron.co.uk

**Penetron-Penecrete-Penebar-Penetron Admix
Penepug/Waterplug**